

The Snow Strike Plan

| Hour | Team A | Team B | Team FLY |
|------|----------------------|------------------------------------|-------------------------------------|
| 0.25 | Remove Wall A | Remove backs from SP | Lower Wall A and reweight |
| 0.5 | | Remove backs from Ground Row | |
| 0.75 | | Remove Stage Portal Lower Sections | Lock off Stage Portal |
| 1 | | | |
| 1.25 | Remove Wall B | Remove Ground Row | Lower Wall B and reweight |
| 1.5 | | | Fly in Electric and reweight |
| 1.75 | | Remove Stage Portal Upper Sections | Lower Stage Portal and reweight |
| 2 | | | |
| 2.25 | Remove Roof | | Lower Roof and reweight |
| 2.5 | | | |
| 2.75 | Remove Bird Poop Box | Remove Snow Mound Rigging | Lower Bird Poop Box and Snow Mounds |
| 3 | Remove Snow Bag | | Lower Snow Bag |
| 3.25 | Reset Soft Goods | | |
| 3.5 | | | |
| 3.75 | | | |
| 4 | | | |

Team A

Lead: Sara

Crew: Ilene

- Remove Wall A

- Unscrew from floor
- Working with fly operator lower flat to the floor
- Remove hogs troughs
 - Store above cloth rack in the paint shop
- Remove rigging hardware
- Unbolt flat
- Remove front facing
 - Send to dumpster
- Remove Side lace flat
 - Send to dumpster
 - Cut in half with Sawsall if necessary
- Remove all staples from 8' flats
 - Place in flat storage

Tools & Equipment

- Screw guns
- Wrench
- Ratchet and socket
- 12' ladder
- Pliers
- End Nips
- Prybar

- Remove Wall B

- Unscrew from floor
- Working with fly operator lower flat to the floor
- Remove hogs troughs
 - Store above cloth rack in the paint shop
- Remove rigging hardware
- Unbolt flat
- Remove front facing
 - Send to dumpster
- Remove Side lace flat
 - Send to dumpster
 - Cut in half with Sawsall if necessary
- Remove all staples from 8' flats
 - Place in flat storage

- Remove Roof

- Working with the fly operator fly in the roof
- Remove from batten
- Remove rigging hardware

- Unscrew 2x4 and send to shop to keep
- Unscrew top frame from the 2x12
 - Send to the dumpster
 - Send the 2x12 to the shop to keep
- Remove Bird Poop Box
 - Working with the fly operator fly in the bird poop box
 - Dismantle the box and keep all hardware
 - Send all wood to the dumpster
- Remove Snow bag
 - Working with the fly operator fly in the snow bag
 - Push any extra snow to the end of the bag and into the trash
 - Untie the snow bag
 - Fold up the snow bag and send to the shop to keep
- Work with Team B and the fly operator to reset the soft goods

Team B

Lead: Natalie

Crew: Nathan

-
- Remove masonite backs from Stage Portal
 - Place 2 full sheets and 1 half sheet on a cart in the shop to be reused
 - Remove masonite backs from ground row
 - Send to dumpster
 - Working with the fly operator remove lower SL 12' section of the Stage Portal
 - Unscrew from the floor
 - Unbolt from the upper section
 - Lower to the floor
 - Cut in half with the Sawsall
 - Send to the dumpster
 - Remove the ground row
 - Unscrew the ground row and send to the dumpster
 - Working with the fly operator remove lower SR 12' section of the Stage Portal
 - Unscrew from the floor
 - Unbolt from the upper section
 - Lower to the floor
 - Cut in half with the Sawsall
 - Send to the dumpster
 - Working with the fly operator remove the upper section of the Stage Portal
 - Lower to the floor
 - Unbolt the flats from each other
 - Remove rigging hardware
 - Send the two 4'x8' flats to the flat storage rack
 - Send the other flats to the dumpster
 - Cut in half with the Sawsall if necessary
 - Remove snow mound rigging
 - Working with the fly operator fly in the snow mound rigging to the deck
 - Remove all rigging and pneumatic parts from the batten
 - Sort and coil the parts and send to the shop to save
 - Remove panel from SR proscenium wall
 - Remove all wires and components

Tools & Equipment

- Screw guns
- Wrench
- Ratchet and socket
- Sawsall
- Prybar

- Send to the shop to save
- Disconnect air hose
- In upper lock rail remove all components of the snow mound system bring to the shop to sort and store
 - Air hose
 - Control wire
 - 2x Black air hose
 - Relay control board
- Work with team A and the fly operator to reset the soft goods

Team Fly

Fly Operator: Lucas
Loading Crew: Bidi, Mason

- Working with Team A lower Wall A
 - Strip line set 14 to pipe weight
- Working with Team B help secure Stage portal
 - Lock off Line set **1**
- Working with Team A lower Wall B
 - Strip line set **16** to pipe weight
- Working with Team B lower Stage portal upper sections
 - Strip line set **1** to pipe weight
- Working with Team A lower Roof
 - Strip line set **8** to pipe weight
- Working with Team A lower Bird poop box
 - Strip line set **7** to pipe weight
- Working with Team B lower Snow mounds
 - Strip line set **18** to pipe weight
- Working with Team A lower Snow bag
 - Strip line set **5** to pipe weight
- Working with Team A and B reset soft goods
 - Move Legs on line set **2** to line set **1**
 - Move Leno Scrim from line set **40** to line set **30**
 - Move Black Scrim from line set **30** to line set **38**
 - Move Blackout curtain from line set **38** to line set **40**